GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Notice dated 12th November 1924.

Notice is hereby given that sealed tenders will be received at the office of the Chief Operator, Cauvery Power Scheme Transformer House, Champion Reefs up to 12th December 1924, for constructing a block of quarters for two clerks at the Transformer Station, Kolar Gold Fields. The tenders will be opened in public at 3 P.M., on Friday the 12th December 1924. The work should be completed within two months from the date of acceptance of the tender.

2. The plans, detailed estimates and conditions may be obtained at the office of the undersigned, between the hours, 8 A.M. to 4 P.M. on any working day.

3. Tenders should be submitted in the usual form and should be accompanied by a statement in the form given below showing the rates at which different items specified will be executed. The rates should be in figures as well as in words.

4. The final acceptance of the tender will rest with the Chief Electrical Engineer who is not bound to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. Each tender must be accompanied with an earnest money of Rs. 100 in cash or Government promissory note and be superscribed "Tender for constructing a block of quarters for two clerks at Kolar Gold Fields" in default of which tenders will be rejected.

6. Within 5 days from the award of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which, his tender will be considered as cancelled and the earnest money will be forfeited.

7. The name of the successful tenderer will be posted in both the offices of the Chief Electrical Engineer to the Government of Mysore, Bangalore and the Chief Operator, Kolar Gold Fields, Champion Reefs in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of any of the tenders, the earnest money on the rejected tenders will be returned.

9. The construction work should be started within 10 days from the notification of acceptance of tender.

Statement showing the approximate quantities of work of constructing one block of quarters for two clerks at Kolar Gold Fields, Champion Reefs.

Item of works	Per	Quantity
Earthwork excavation and filling in basement	C. yd.	39
Chunam concrete foundation	C. ft.	1,05[illegible]
Stone in mortar foundation basement	,,	658
Burnt brick in mortar superstructure	,,	2,25[illegible]
Stone slabs 6" thick roughly dressed	S. ft.	127
Chunam plastering	Sqr.	42·71
Chunam pointing	,,	124
White and colour washing, 2coats	,,	43·95
Concrete flooring 3" thick with chunam plaster on top	,,	5·04
Flooring with Cuddapah slabs on 3 concrete and cement pointed	,,	1·52
Honey wood work with wood oiling	C. ft.	31·02
Roofing with 1st class Mangalore tiles on honey wood reepers 2"x1" and cement pointing the top surface.	Sqr.	12·60
Ridge tiles set in mortar and cement pointing	R. ft.	30
Honey wood battered doors 1½" thick, complete	S. ft.	182
Do do windows with iron bars 5/8" dia., etc., complete	,,	48
Honey wood glazed ventilators, complete	,,	12
Chocolate painting 3 coats	Sqr.	4·72
Chunam putty	R. ft.	82
Ventilating tiles	No.	8
Providing mortar and pestle	,,	2
Teakwood plank 1" thick for shelves	S. ft.	18

LOUIS. J. GORDON,
Chief Operator.

KOLAR DISTRICT TREASURY.

Notice, dated 13th November 1924.

The Savings Bank Depositors of the District and Taluk Treasuries are requested to present their Pass Books at the respective Treasuries for adding interest for 1923-24.

S. HIRIANNAIYA,
Deputy Commissioner,
Treasury Department.